

Annexure -I

PRICE BID(FORM 1 - B)

Work Schedule / BOQ for Removal of mud, sand and slushy earth at catchment area of raw intake System, OTPC, Palatana.

Sl.No	TSR 2017 item no	Description of Item	Unit	Total Qty	Rate (Rs.)
1	Quotation Rate	Cleaning & desilting of sand and earth from forebay and riverbed at river water intake system, OTPC Palatana and carriage of earth up to OTPC premises.		10800.00	₹ 200.00
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- All works upto plinth level-			
	4.1.5	1:3:6 (1 Cement: 3 fine sand : 6 graded stone aggregate 20 mm nominal size)	Cum.	6.60	₹ 8,814.38
3	5.8	Centring shuttering including struttings, propping etc. and removal of form work for:			
	5.8.1.1	Foundations, footings, bases for columns etc. for mass concrete with timber plank	Sq.m.	10.20	₹ 240.09
4	6.1	First class brick work in foundation and plinth including cost of all materials as required complete:-			
	6.1.4	In cement mortar 1:5 (1 cement:5 fine sand).	Cum.	5.00	₹ 7,809.02
5	12.1	12 mm cement plaster in single layer including cost of materials required and finishing even and smooth and curing complete.			
	12.1.2	In cement mortar 1 : 4 (1 cement : 4 fine sand)	Sq.m.	15.00	₹ 156.07
6	12.2	15 mm cement plaster on the rough side in of single or half brick wall of mix layer including cost of materials required and finishing even and smooth and curing complete.			

	12.2.2	In cement mortar 1 : 4 (1 cement : 4 fine sand)	Sq.m.	20.00	₹ 181.61
		Total Rs :			
		Rate/Percentage Less%			
		GST @ 18 % HSN/SAC Code : 995416			
		Grand Total Rs:			
		(Rupees			

water entry channel to River water

Total Amount (Rs)	Remarks
2160000.00	The Vendor had quoted combined rate.
	These qty taken if any damage happened during earth work desilting.
58174.91	
	These qty taken if any damage happened during earth work desilting.
2448.92	
	These qty taken if any damage happened during earth work desilting.
39045.10	
	These qty taken if any damage happened during earth work desilting.
2341.05	
	These qty taken if any damage happened during earth work desilting.

3632.20	
2265642.18	
.....only)	